

SECTION 00 11 15 - ABBREVIATED SCOPE OF WORK

THE FOLLOWING IS AN ABBREVIATED SCOPE OF WORK INTENDED TO PROVIDE POTENTIAL BIDDERS WITH INFORMATION AS TO THE SIZE AND NATURE OF THE PROJECT. BIDDERS ARE TO REFER TO THE DRAWINGS AND SPECIFICATIONS FOR THE COMPLETE SCOPE OF WORK.

Project: 20083.00 Allen County Board of DD, Addition & Renovation to Administrative Building

**2500 Ada Road
Lima, Ohio 45801**

GM Project Number: 20083.00

Bid Date: 11:00:00 AM on Thursday, December 15, 2022

Bid Categories: Lump Sum General Contract

Estimate of Construction Cost: \$1,250,000.00 (One million, two hundred and fifty thousand dollars)

PROJECT SCOPES OF WORK

General Construction:

Interior office renovation of approximately 4,300 square feet and 1,344 square feet addition. Demolition of existing items noted on drawings including existing exterior walls, roof structure, flooring, base, ceiling, casework, storefronts, and any other demolition items indicated on the plans. New exterior concrete masonry walls with face brick veneer and roof structure consisting of wood trusses and an asphalt shingle roof system. New hollow metal door frames with hollow metal doors, hollow metal door frames with wood doors, and aluminum framed storefronts, complete with door hardware, and glazing. New Metal stud and drywall wall construction with acoustical ceilings with drywall bulkhead as indicated on the ceiling plan. Flooring to include sheet carpeting. Painting as indicated on drawings and new furniture in select offices as shown on the drawings.

Site Work:

Site work includes demolition of concrete, curbs and other items as shown on the drawings. Installation includes storm, concrete, seed, and items as shown in the drawings.

Plumbing Work:

Plumbing work consists of, but not limited to demolition of existing items noted on drawings including sink, washing machine box and associated accessories. Demolition of all associated piping back to main where they are to be capped. Demolition of existing natural gas piping serving exiting furnace in the mechanical room. New gas piping to serve new furnace.

HVAC Work:

HVAC work consists of, but not limited to demolition of existing diffusers, ductwork, furnace, condensing unit and associated accessories. Installation of new ductwork, diffusers, furnace, condensing unit and associated accessories. Installation of a 2-zone control damper system in new system and installation of an 8-zone control damper system in an existing system.

Electrical Work:

Electrical work consists of, but not limited to demolition of power, fire alarm, lighting devices, light fixtures, mechanical equipment and technology devices. New work consists of fire alarm, power to new receptacles (surface raceway where required), and mechanical equipment. Also, new LED lighting throughout the existing, renovation space, and the new addition controlled by occupancy sensors, and low voltage switches.

Technology Work:

Technology work consists of but is not limited to horizontal communications cabling, audio and video cabling and equipment, sound reinforcement systems and intrusion detection systems.

END OF SECTION