

## **SECTION 00 11 30 - ABBREVIATED SCOPE OF WORK**

**THE FOLLOWING IS AN ABBREVIATED SCOPE OF WORK INTENDED TO PROVIDE POTENTIAL BIDDERS WITH INFORMATION AS TO THE SIZE AND NATURE OF THE PROJECT. BIDDERS ARE TO REFER TO THE DRAWINGS AND SPECIFICATIONS FOR THE COMPLETE SCOPE OF WORK.**

**Project: 22087.00 Hardin Co. Annex Building Brick Repair  
175 W. Franklin Street  
Kenton, Ohio 43326**

**GM Project Number: 22087.00**

**Bid Date: February 28, 2023 at 10:30.00 AM**

**Bid Categories: Lump Sum General Contract**

**Estimate of Construction Cost: \$ 200,000**

### **PROJECT SCOPES OF WORK**

#### **General Construction:**

The project consists of removal of the brick veneer within approximately 2 feet of the building corners and rebuilt to properly anchored to the existing metal stud walls with new veneer ties.

Additional work associated with cutting out the existing relief joints in their current location. These joints are to then be filled with appropriate backer bar and sealant.

**END OF SECTION**

This page intentionally left blank